

Product- Rice Flakes

Sl.	Type of machine	Specification	No. of Unit	Unit Cost	Total Amount
1	Vacuum Evaporater-Tomato paste	Material- Stainless Steel- 304, Evaporate capacity- 50 kg/hour, Concentrator tank volume- 200 L, Evaporate temp- < 60 degree celsius, Steam consumption kg/hr- 56	1	500000	500000
2	Hammer Mill for tomato paste	Material- Stainless Steel-304, Automation grade- Semi-automatic, Capacity- min 500 kg/hour	1	150000	150000
3	Tubular Juice pasteurizer	Material- Stainless Steel 304, Automation grade- Automatic, Capacity- min 200 lt/hour, Temp profile- 95 degree celsius	1	500000	500000
4	Baby Steam Boiler	Capacity- up-to 500 kg/hour, Type- Wood fired Steam Boiler, Material- Mild Steel, Working Pressure- Min 5 kg/sq.cm.g, Style- Vertical	1	175000	175000
5	Tomato pulper	Material- Food grade stainless steel, Capacity- Min 200kg/hour, Driven type- Electric	1	75000	75000
6	Tomato sauce filling machine	Type of sealing- Centre sealing, Material- Food grade Stainless steel, Driven type- Electric 3 Phase, Filling system- Automatic, Packaging type- Pouch, Speed- min 300 pouch/hr	1	350000	350000
7	Tool-kit for distribution: Agriculture tool-kits	Hand tools Kits set (Secateur, Trowel, Hoe, Fork, Weeder, cultivator, transplanter, hand sickle)	202	2500	505000

8	Computer	All- in One Desktop Computer. Processor: Intel i3 or equivalent AMD RAM 8 GB DDR 1 TB SATA HDD 19" LCD Monitor UPS 650 VA	1	60000	60000
9	Printer	Multi function printer (Printer/Scanner/Copier) RAM Size : 8 MB Hardware Interface: USB Print Colour: Monochrome Printing Technology: Laser Resolution: 1200 dpi Max scanning size: A4	1	20000	20000
10	Steam Jacketed Kettle	Tilting Arrangement- Tilting type (through worm gear/pinion) Material: Stainless Steel SS 304 Phase: Single Phase Capacity: 250 to 300 Liters Other Specification: Kettle bottom should be of hemispherical design, the unit should be complete with pressure gauge, safety valve, steam pet cock, Steam trap	1	100000	100000
11	Other accessories to operationalise the Tomato sauce processing line	Incl. screw pumps, pipes and fittings, elevator buckets etc.	LS		300000
Total					2735000

